

Project Brief

Denver Water Pipe Strengthening



Denver, CO
2008



Denver Water experienced a catastrophic failure when a section of 66-inch steel pipeline that conveys water to the northern part of the City, failed due to a sudden rise in surge resulting from a pump failure.

Fibrwrap Construction was contracted by Denver Water to utilize the patented Tyfo® Fibrwrap® Pipe Rehabilitation System to structurally retrofit the line, installing the required carbon-based Tyfo® SCH-41-2X System in the hoop direction, allowing the pipe back into working pressure capacity as well as accounting for surge pressures.

This method of structural retrofit was selected because no other options were available which would enable a completely trenchless renewal of this magnitude. Both slip-lining and remove-and-replace were prohibitive as the line was located directly underneath the heavily traveled Interstate 25.

The project was completed on schedule and within budget enabling Denver Water to place the line immediately back into service.

Fyfe Co. LLC

8380 Miralani Drive, Suite A, San Diego, CA 92126

Tel: 858.642.0694 Fax: 858.444.2982 Email: info@fyfeco.com www.fyfeco.com